

ADDENDUM NO. 2
WATER SYSTEM IMPROVEMENTS
CONTRACT 17-02
HOLIDAY AND MEADOW PARK WTP IMPROVEMENTS
CROSSVILLE, TENNESSEE
WAUFORD PROJECT NO. 4628

Date of Addendum: Friday, August 4, 2017

Bid Opening: Tuesday, August 8, 2017, 2:00 P.M. Local Time

1. The following Paint Suppliers are pre-qualified to submit bids for Contract 17-02 – Holiday and Meadow Park WTP Improvements:

Tnemec

2. Detailed Specifications, Section 6. Miscellaneous Equipment, Paragraph 2.d. Chemical Transfer Pumps, Page DS 6-2:

Modify the paragraph to read as follows:

“The Contractor shall furnish and install as shown on the Plans **two (2)** magnetic drive chemical transfer pumps for the following chemicals: coagulant (polyaluminum hydroxychlorosulfate) or caustic (sodium hydroxide 50% concentration).”

3. Questions and Clarifications:

See attached Questions and Clarifications.

J. R. WAUFORD & COMPANY,
CONSULTING ENGINEERS, INC.



Scott B. Carroll, P.E.
Tennessee License # 116799

WATER SYSTEM IMPROVEMENTS
CONTRACT 17-02
HOLIDAY AND MEADOW PARK WTP IMPROVEMENTS
CROSSVILLE, TENNESSEE
WAUFORD PROJECT NO. 4628

Questions/Answers and Clarifications:

1. Can EMT conduit be used in attic spaces and inside walls at the Meadow Park WTP?
No. Rigid Galvanized Steel should be used as specified.
2. Are seal offs required on this project?
No.
3. Is a Building Permit Required? If so who is the contact and what is the price?
Yes. Jeff Kerly is the contact. His number is 931-456-1830. The fee will be waived.
4. What area is considered to be the chemical containment area for painting purposes?
The floor of the chemical room, troughs, and chemical containment area at the back of the building should be considered the chemical containment area for painting purposes.